ROOF DESCRIPTION
ROOF TYPE ASPHALT SHINGLE
ROOF # OF MODULES
#1 12 18 170

BILL OF MATERIALS

EQUIPMENT	QTY	DESCRIPTION
SOLAR PV MODULES	42	SIRIUS SOLAR ELNSM54M-HC-N 450W
MCI's	14	TESLA: RSD MCI-2
INVERTER/BATTERY	02	TESLA POWERWALL 3 (1707000-xx-y)
EXPANSION	01	TESLA POWERWALL 3 EXPANSION (1807000-xx-y)
GATEWAY	01	TESLA BACKUP GATEWAY 3, 200A, NEMA 3R RATED, 120/240V (1841000-x1-y)
RSD	01	IMO RAPID SHUTDOWN SWITCH (PE69-3020)
RAILS	33	EVEREST K2 SYSTEMS CROSSRAIL 44-X MAX RAIL
SPLICE	16	SPLICE KIT
MODULE CLAMPS	56	MID MODULE CLAMPS
END CLAMPS	56	END CLAMPS
DC DISCONNECT	1	DC DISCONNECT, 32A/600V, 4 POLE
DC DISCONNECT	2	DC DISCONNECT, 32A/600V, 2 POLE
PHOTOVOLTAIC/ENERGY STORAGE SYSTEM AC DISCONNECT	02	60A NON-FUSED PHOTOVOLTAIC/ENERGY STORAGE SYSTEM AC DISCONNECT 240V NEMA 3R, UL LISTED (DU222RB)
ATTACHMENT	32	K2 MULTIMOUNT ATTACHMENTS (DECK MOUNTED)
ATTACHMENT	112	S-5! PROTEA BRACKET ATTACHMENTS